ERIE MATERIALS
BUILDING PRODUCT SOLUTIONS

Roofing Estimate Sheet

Date: 03/18/14

Syracuse Location 500 Factory Ave. (315)455-7434 FAX:(315)455-9275

Job Name: DOE Student Challenge
Address: -
County: Onondaga
Tax Rate: 8.000%
Customer: Montage
Contact: -
Phone: -
Cell: -

Prices on this estimate are valid for : 30 Days

QTY	U/M	Description	Price		Extended
28	SQ	Certainteed *Solaris* LEED Certified Lifetime Shingles (250 lbs/sq)	202.95	$	5,682.60
		Lifetime Warranty (Residential) 50 Year Warranty (Commercial Buildings)			
3	BDL	Certainteed SOLARIS Hip & Ridge (33')	79.95	$	239.85
4	RL	15# Felt (4 sq rl)	24.95	$	99.80
8	RL	Certainteed WinterGuard Ice & Water (2 sq rl)	61.95	$	495.60
40	PC	White Galvanized Drip Edge 1"	3.85	$	154.00
19	PC	Air Vent Shingle Over Ridge Vent 4' pc	10.40	$	197.60
2	BDL	Certainteed Swift Start Starter (116 LF)	39.95	$	79.90
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
		Freight, Fuel, and/or Stopover Charges may apply	-	$	-
			Sub-Total:	$	6,949.35
			8.00% Tax	$	555.95
			Total:	$	7,505.30

Verification of all quantities, sizes and specifications are the responsibility of the contractor.

estimated by: my

checked by: st

This is an estimate based on our interpretation of the specifications and drawings dated: NA

ERIE MATERIALS
BUILDING PRODUCT SOLUTIONS

Roofing Accessories Estimate Sheet

Date: 03/18/14

Syracuse Location 500 Factory Ave. (315)455-7434 FAX:(315)455-9275

Job Name: DOE Student Challenge
Address: -
County: Onondaga
Tax Rate: **8.000%**
Customer: Montage
Contact: -
Phone: -
Cell: -

Prices on this estimate are valid for : 30 Days

QTY	U/M	Description	Price		Extended
2	RL	14" Aluminum Flashing (50' rl)	29.95	$	59.90
1	BDL	Pre Bent Step Flashing (mill finish)	15.50	$	15.50
10	LB	2-1/2" Hand Roofing Nails	1.15	$	11.50
2	BOX	Generic 1 1/2" Coil Roofing Nails	29.95	$	59.90
3	TB	Karnak Amphibicaulk	2.25	$	6.75
2	EA	1"-3" Pipe Flashing	5.95	$	11.90
2	EA	3"-4" Pipe Flashing	7.25	$	14.50
2	PK	5/16" Arrow Staples	7.95	$	15.90
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			-	$	-
			Sub-Total:	$	195.85
			8.00% Tax	$	15.67
			Total:	$	211.52

Verification of all quantities, sizes and specifications are the responsibility of the contractor.

estimated by: my

checked by: st

This is an estimate based on our interpretation of the specifications and drawings dated: NA