HEALY

PLUMBING & HEATING, INC.
840 W. BELDEN AVENUE' SYRACUSE, NY 13204
(315) 476-4626 FAX (315) 476-8660
EST 1924

PROPOSAL

TO: MONTAGE BUILDERS –
NORTHERN FOREST

ATTN: Michelle Tinner

DATE: 3-24-14
PHONE/FAX: 239-682-2462
NAME: US DOE Project
LOCATION: 203 Hubbell Ave
Syracuse, N.Y.

We are pleased to provide you with a proposal for labor/ material for the complete installation of a 2- Zone Hydronic Radiant Heat System for the above referenced project that include the following:

- Equipment: Provide labor/ material to install, test and start-up as per manufactures specifications equipment package provided by others. "Daikin" Altherma condensing unit, Hydro box and 80 gallon Domestic HWH by others. Install, test and evacuate all refrigeration piping from outdoor unit to indoor Hydrobox. Shop fabricate boiler panel with all piping for complete system with air scoop, expansion tank, water feed system. Install all required supply/ return piping for HWH.

- Radiant Tubing: Provide labor/ material to install two complete zones of "staple-down" radiant tubing, including approx. 2,800' -1/2" pex radiant tubing with 1,100 aluminum heat transfer plates, install ¾" PEX supply/ return piping from boiler panel to zone manifolds, zone manifolds. Install 2- Taco ESP Zone valves, 1- ½" pressure differential by-pass valve.

2- Zone Hydronic Radiant System Installation.....$8,250.

NOT IN CONTRACT

- Daikin Equipment, Power supply for DHW booster heater, system anti-freeze if required, pipe insulation, system circulating pumps (provided in hydrobox)

We propose hereby to furnish material and labor - complete in accordance with these specifications, for the sum of ********* dollars and 00/100 ********* dollars ($..).
Payable as follows: *Balance 30 days* *2% Finance Charge on Past Due Accts*

Healy Plumbing & Heating, Inc. Authorized Signature:

All material is guaranteed to be as specified. All work will be completed in a workmanlike manner according to standard practices. Any alteration or deviation from the above scope of work involving extra costs will be executed only upon written orders, and will become an extra charge over and above this estimate. All agreements are contingent upon strikes, accidents or delays beyond our control. Owner to carry fire, tornado, and other necessary insurance.
Our workers are fully covered by Workman's Compensation Insurance.
This proposal may be withdrawn if not accepted within 30 days or as indicated above.
ACCEPTANCE OF PROPOSAL - The prices, specifications and conditions are satisfactory and are hereby accepted. You are authorized to work as specified. Payment will be made as outlined above.

Signature: Company: