Emissions

Property
TBD
201 Hubbell Ave
Syracyse , NY 13207

Weather:Syracuse, NY
The Montage Solar
DOE House wSolar FINAL.blg

Organization
MBT Design
(845)520-9110
Michelle Tinner

Builder
Montage Builders - NF

HERS
Projected Rating
3/17/14
Rating No:1
Rater ID:2636162

Emissions By End-Use

	The Montage	The Montage Solar	Savings	%Saved
Carbon Dioxide (CO2) - tons/year				
Heating	1.0	0.9	0.0	2.6%
Cooling	0.0	0.0		
WaterHeating	0.5	0.0	0.5	98.2%
LightsAppliances	1.8	1.8		
Photovoltaics	0.0	-3.3	3.3	
Total	**3.2**	**-0.5**	**3.8**	**116.4%**
Sulfur Dioxide (SO2) - lbs/year				
Heating	2.5	2.4	0.1	2.6%
Cooling	0.0	0.0		
WaterHeating	1.3	0.0	1.3	98.2%
LightsAppliances	4.6	4.6		
Photovoltaics	0.0	-8.4	8.4	
Total	**8.4**	**-1.4**	**9.8**	**116.4%**
Nitrogen Oxide (NOx) - lbs/year				
Heating	1.4	1.4	0.0	2.6%
Cooling	0.0	0.0		
WaterHeating	0.7	0.0	0.7	98.2%
LightsAppliances	2.6	2.6		
Photovoltaics	0.0	-4.7	4.7	
Total	**4.7**	**-0.8**	**5.5**	**116.4%**

Site-to-source energy multipliers and air emission data were taken from the US EPA eGRID2007 database.

This information does not constitute any warranty of energy cost or savings.
© 1985-2014 Architectural Energy Corporation, Boulder, Colorado.